PROJECT PDF

Willemen Groep
Boerenkrijgstraat 133, BE - 2800 Mechelen
tel +32 15 569 965, groep@willemen.be

Ecoduct Kempengrens - Mol

Project Details

Activities
Civil Engineering
Bridges

Contractors
Willemen Bouw

location
E34 kilometerpaal 57.8
2400 Mol Belgium
Antwerpen BE

Client
Agentschap Natuur en Bos,
Agentschap Wegen en Verkeer,
Provincie Noord Brabant Nederland

Architects
Agentschap Wegen en Verkeer
Afdeling expertise beton en staal

Engineering Office
Agentschap Wegen en Verkeer,
afdeling expertise beton en staal

Span
68m

Surface area above ground
4 250m²

Surface area subterranean
2 870m²

Construction period
11 months

Start work
08-2013

Franki Construct built the ‘Kempengrens’ ecoduct [wildlife crossing] at the hamlet of Postel, in the municipality of Mol, which is near the Belgian-Dutch border. It is a bridge structure over the E34 that allows local fauna to get over the motorway in safety. The project is a collaboration between the Flemish and Dutch governments and aimed at reducing the negative impact on the local ecosystem caused by the man-made road infrastructure. The specific design and location of the bridge ensures maximum integration within the natural surroundings.

The minimum width of the ecoduct is 60 metres and it features a special diabolo-like design that continues on into the land abutments. The walls are arched and refer to the twisting movement of snakes, being one of the animal types that will make frequent use of the ecoduct. The bridge is constructed from reinforced, high-strength concrete (C40/50) and the land abutments from traditional, strong concrete (C35/40). The abutments have been conceived as a hollow volume, instead of a single, thick wall. The rounded shapes of the bridge, the hollow cavities in the abutments and the oval-shape of the central pillars demanded a specific type of shuttering. This ecoduct is certainly not a standard bridge. Throughout the period of the construction work it was essential that the E34 motorway remained open in the direction of Antwerp and Eindhoven with respectively two and one lanes.

Some key figures:

© Willemen Groep

End of work
07-2014

32,000 m special fencing for fauna
15,000 m³ concrete
1,325,000 kg reinforcements
6,900 m pre-stressing (pipes)
90,000 m³ earth fill.

Willemen Bouw

Boerenkrijgstraat 133
2800 Mechelen, Antwerpen
(Belgium)
tel +32 3 450 77 00
bouw@willemen.be
www.willemen.be

Willemen Bouw was established on 30 April 2025 through the merger of Willemen Construct, Cosimco, Franki Construct and Tools.